

WASHINGTON MILITARY DEPARTMENT
Construction Facilities Management Office
Camp Murray
Grandview Readiness Center HVAC Replacement
PROJECT NUMBER # 2015-665
RFP-17-GS-011

TO: ALL PLANHOLDERS

ADDENDUM NUMBER #01

This addendum shall be bound into and become part of the above referenced project. Bid documents for the project shall be modified as follows:

1. This addendum applies to the Grandview Readiness Center HVAC Replacement project located at Grandview WA..
2. Section 23 74 00 Package Rooftop Units.

Item 1.01B Related Sections. Add Section 23 09 00 DDC Controls

**Item 0.02.6 Delete and replace with
Factory installed 0-10 VDC modulating economizer damper wired to terminal strip
for direct control by section 23 09 00 (DDC Controls)**

**Item 0.02 Add new line item. Add 12. Damper, heating, cooling, auxiliary heat
and fan operation control shall be wired to factory terminal strip for direct control
by section 23 09 00 (DDC Controls)**

3. The question was asked, AH5 has exterior insulation applied to the duct work if new duct is necessary would interior insulated duct be acceptable?
Yes, interior insulation that meets energy code is acceptable.

Acknowledge receipt of this addendum on the Bid Proposal form in the space provided.

END OF ADDENDUM NUMBER #01

