

WASHINGTON MILITARY DEPARTMENT
Construction Facilities Management Office
Camp Murray
Pasco Readiness Center HVAC Replacement
PROJECT NUMBER # 2015-666
RFP-17-GS-010

TO: ALL PLANHOLDERS

ADDENDUM NUMBER #01

This addendum shall be bound into and become part of the above referenced project. Bid documents for the project shall be modified as follows:

1. This addendum applies to the Pasco Readiness Center HVAC Replacement project located at Pasco WA..
2. Section 23 74 00 Package Rooftop Units.

Item 1.01B Related Sections. Add Section 23 09 00 DDC Controls

**Item 0.02.6 Delete and replace with
Factory installed 0-10 VDC modulating economizer damper wired to terminal strip for direct control by section 23 09 00 (DDC Controls)**

Item 0.02 Add new line item. Add 12. Damper, heating, cooling, auxiliary heat and fan operation control shall be wired to factory terminal strip for direct control by section 23 09 00 (DDC Controls)

3. The project specifications do not call for new installed duct work to be painted.
Add section 09 91 00 Painting.

Part 1-Product

1.1 Materials

Provide paint and related products for prime, intermediate and finish coats, of type brand and manufactures listed in APSM, chapter 5, latest edition, factory labeled for positive identification in accordance with finishing Schedule hereafter. Swerwin Williams used.

1.2 Finishing Schedule, interior surfaces.

New exposed non ferrious metal (including galvanized): interior 5.2A “premium grade” pre-treatment primer, cementitious primer, 2-coats interior latex enamel semi gloss. Primer B66W00310-pro industrial pro-cyrl universal acrylic primer off white, 2 coats B66W1151- pro industrial DTM acrylic semi gloss.

Acknowledge receipt of this addendum on the Bid Proposal form in the space provided.

END OF ADDENDUM NUMBER #01

